

Boston Washington Reston New York New Haven Los Angeles

London



701 Pennsylvania Avenue, N W Washington, D C 20004 202 434 7300 202 434 7400 fax www mintz com

Russell H. Fox

Direct dial 202 434 7483 tfox@mintz.com

EX PARTE OR LATE FILED

April 29, 2004

FILED ELECTRONICALLY AND BY HAND

Marlene H Dortch Secretary Federal Communications Commission 445 12th Street, S.W. Washington, D.C. 20554

APR 2 9 2004

RFCEIVED

THE COMMUNICATIONS COMMINGHON

Re: Notice of Ex Parte - WT Docket No. 03-103: A

Notice of Ex Parte - WT Docket No. 03-103: Amendment of Part 22 of the Commission's Rules to Benefit the Consumers of Air-Ground Telecommunications Services; Biennial Regulatory Review Amendment of Parts 1, 22, and 90 of the Commission's Rules

Dear Ms. Dortch:

Pursuant to the provisions of Section 1.1206(b) of the rules and regulations of the Federal Communications Commission ("FCC"), The Boeing Company ("Boeing") hereby submits this letter summarizing its *ex parte* presentation in the above-referenced proceeding. On April 28, 2004, Guy Christiansen, Mike de la Chapelle, Sean Schwinn, and Audrey Allison of Boeing and Howard Symons and Russell Fox of Mintz, Levin, Cohn, Ferris, Glovsky, and Popeo, P.C. met with Richard Arsenault, B.C. "Jay" Jackson, Jr., Shellie Blakeney, Roger Noel, Moslem Sawez, David Furth, and Thomas Derenge of the Wireless Telecommunications Division and Bruce Romano, Ira Keltz, and George Sharp of the Office of Engineering and Technology to discuss the attached presentation.

A copy of this letter and presentation is being submitted manually to you because the FCC's Electronic Comment Filing System ("ECFS") will not accommodate the video component of the presentation. Accordingly, the electronically submitted version contains only a Power Point file. The manually submitted version has a copy of that Power Point file and a compact disc containing the video component of the presentation.

MINTZ, LEVIN, COHN, FERRIS, GLOVSKY AND POPEO, P.C.

Marlene H. Dortch April 29, 2004 Page 2

Should there be any questions regarding this matter, please contact the undersigned directly.

Cordially yours,

Zurem 717

Russell H. Fox

Attachment

cc by (e-mail) Richard Arsenault

B.C. "Jay" Jackson, Jr.

Shellie Blakeney Roger Noel Moslem Sawez David Furth Thomas Derenge Bruce Romano

Ira Keltz George Sharp

WDC 348961v1

Overview



- Simple rules
- "Plain old base station" technology
- Simple aeronautical antenna less expensive than many deployed today




- Three service providers can share spectrum
- Concerns of other participants addressed
- Accommodates transition of the incumbent system



- Gives service providers maximum latitude to choose technologies and system design
- Encourages efficient use of ATG spectrum
- Allows service providers to upgrade technology
- Open items can be addressed via comments within current NPRM


ATG Technical Thesis & Solution




<u>Thesis</u>


Spatial isolation provided by sectored base station antennas, directional aeronautical antennas, and the curvature of the earth, allow multiple service providers to serve the entire addressable market while sharing the existing ATG spectrum.

Directional Aircraft Antenna




7-Element Array






Elevation Cut

Simple and inexpensive aero antenna provide >10 dB spatial isolation.



Weight ~ 10 kg (22 lbs)

Note: Substantially improved performance can be achieved by bore sighing away from interfering base station or adaptive nulling.





Pointed to Horizon

4

"Plain-Old" Base Station Antenna 6-Sectors (60°)










Andreas Coperation


Fee: 214.001.4708 TellFree Tell TRODE:06.6142 Fee: 1 BQL 220.4700

08e003, commi OBSORIAL Assesseds What May are






6-Sector Mast-Mounting Configuration



This product has been in production for twenty years. Same product line includes 45° (8sector) and 35° (10sector antennas

ATG Spectrum Channelizat



Our channelization plan:


- accommodates 3 systems (more with state-of-the-art technology)
- ·provides a transition plan
- Uses overlapped 1.25 MHz channels to accommodate all CDMA2000

Proposed ATG Rules

Two Approaches That Work


- •We studied different approaches for co-freq sharing between multiple CDMA systems.
- We found two opposite approaches that technically work.

Separated & Uncoordinated Base Stations



- •Requires no coordination between systems
- Service providers are free to choose technology and standards
- •Service providers can independently upgrade their networks
- •Requires minimum separation distances between base stations
- Requires emission level limits for BTS and aircraft

Common & Coordinated Base Stations



- Similar to current ATG rules
- Requires service providers to share base stations*
- Locks service providers into current standards and technologies
- Prevents system upgrades and innovation
- Discourages efficient use of spectrum

*Current rules require co-location of base stations within several miles CDMA with shared Walsh codes requires less than 30m separation between antennas, which is effectively the same tower. Shared BTS are becoming increasingly common

- •We recommend separated & uncoordinated base stations
- Proposed rules & analyses are based on this approach

Rule Strategy

- Make rules as simple as possible.
- Do not require any coordination or synchronization between service providers and base stations.
- Allow service providers to implement their systems with whatever design and technology they choose.
 - Do not mandate any antenna implementation
 - Do not mandate any particular CDMA standard
- Rules are designed to encourage efficiency & limit interference


Proposed Base Station Separation Distance Rules

- Inter-System BTS Separation Distance
 - Base stations (BTS) from different systems shall be separated by at least 131 miles (211 km).
- Intra-System BTS Separation Distance
 - Base stations (BTS) from the same system shall be separated by at least 227 miles (366 km).


These separation distances allow:

- Continuous coverage above 10,000' AGL
- Accommodates 3 systems on irregular grid.

BTS Separation Distances – Regular Grid



Inter-System BTS Spacing vs # of Systems



- •Inter-System BTS spacing reduces as number of systems increases.
- •More sophisticated technology is required to isolate the serving BTS as the # of systems increases
- ·Analysis shows that 4 systems can be accommodated at a BTS spacing 131 miles

BTS Spacing - Justification

- The intra-system spacing must be within the radio horizon-to-horizon (RH-H) distance from the aircraft.
 - Radio horizon (RH) distance for an aircraft at 10,000' to a 50' base station on level ground is 151 miles (244 km) or 302 miles (488 km) RH-H.
 - The proposed intra-system separation distance (227 miles) is well within the RH-H of 302 miles which allows for uneven terrain effects.
- The previous analysis shows that 131 miles inter-system BTS spacing is consistent with 4 service providers in regular grid. Analysis shows that this configuration works.
- To increase flexibility in base station placement, 3 systems are used with the same inter-system BTS separation, allowing the intra-system separation to be reduced 227 miles.
- This allows considerable latitude for off-grid placement of base stations.
 - Separation between 227 miles and the RH-H are possible.

EIRP Limit Rules

- The EIRP spectral density emitted from any base station shall not exceed X dBW/Hz in any direction within the ATG band.
- station shall not exceed X dBW/Hz in the direction of that base The aggregate EIRP spectral density from all aircraft operating station and within the ATG band. on one system within the radio horizon of another system's base


CDMA standard or technology (BTS and aero antenna designs). These rules allow service providers the freedom to choose any

Simulation Results

Simulation Objectives

- Simulation #1 Prove the Geometry
 - Show that the geometries of multiple system operation avoid scenarios that can produce unacceptable inter-system interference.
 - The "near-far" problem never occurs for the 3 or 4-provider solution.
 - Provide the FCC with a visual demonstration that proves that the geometries work.
- Simulation #2 Measure system capacity for multiple system scenarios.
 - Vary traffic intensity up to full market load.
 - Determine how many service providers can share ATG spectrum.
 - Evaluate sensitivity to design parameters and technologies.

4-System Geometry – Video Simulation



Aircraft "flown" from
Washington, DC to Seattle, WA
Connects to blue service
provider's base stations
Interfering base stations are
colored red, yellow and green.

<u>Video #1 – Hemi antenna @ 30'K</u> <u>Video #2 – 7-Element Array @ 30'K</u>




Results:

<u>Hemi-Antenna</u>
•Near-Far problem occurs
over most of flight

7-Element Array
Near-Far problem never occurs.

4 Systems Geometry – Regular Grid



Near-Far problems are completely eliminated by use of directional aero antenna. >4.8 dB Far/Near squared ratio provides sufficient Eb/lo.

Full Simulation

- Measure system capacity
- Determine max number of systems.


Simulation Assumptions


- Nearest BTS coverage
- No coordination between BTS
- Inter-system BTS location spacing for 4 systems (see rules)
- Traffic load = 10, 20, 50, 80,100% of market
 - Market assumptions follow
- No traffic below 10,000'

- 64 orthogonal Walsh codes (out of 128 available)
 - Re-used per sector
- Vertical polarization only
- Directional aero antennas
 - See model
- Single 1.25 MHz CDMA channel up & down.
- Results multiplied by 1.375 to account for second overlapped channel.
- Limited aircraft EIRP (see rules)
- Limited base station EIRP (see rules)
- Ignore multi-path.

Market Definition

- All scheduled flights between North American city pairs
 - Reference OAG
 - Aircraft having greater than or equal to 100 seats
- Flights longer than 1 hour
- 23,333 Such Flights Flown on Friday





Estimating Average Aircraft Data Rates

Number of Concurrent Broadband Users



737 ~200 Seats



Seat Load Factor 75% 150 Passengers



Penetration Rate 20% 30 Customers




Activity Factor 50% 15 Concurrent Users

Broadband User Demand Aggregation






- On-board Avg Single User Data Rate = 12 kbps
- Off-board Avg Single User Data Rate = 3 kbps



- Average Aggregate On-board Aircraft Data Rate = 180 kbps
- Average Aggregate Off-board Aircraft Data Rate = 45 kbps


Simulation Algorithm

- →Fly alireraft on OAG schedule



- Calculate aggregate interference into each aircraft from all BTS within RH
- Calculate aggregate interference into each BTS sector from all aircraft within RH
- Calculate EIRP for each aircraft to close link to BTS in presence of said interference
- Calculate EIRP for each BTS to close link to each aircraft in the presence of said interference
- Loop until solution converges
- Move all aircraft forward one time step

Simulation Results




Conclusions

- •Small percentage of links do not close at 100% market loading using 6-sector BTS.
- •All links close with 10-sector BTS and 100% market loading.
- ·Results are even better with asymmetric loading between systems.

Capacity Density and Verizon System Changes

- It is more spectrally and economically efficient for service providers to increase local capacity by BTS sectorization rather than deployment of additional BTS.
- There is localized capacity saturation in the mid-west and northeast when only 6-sector antennas are used.
- Our simulation employs several 10-sector base stations in the densest traffic regions.
- Airfone's current network has excess base stations that are unnecessary for achieving capacity.
- Proposed separation rules require changes to Airfone's system:
 - 40 stations unused
 - 20 stations moved
 - -+77 of original base stations remain active in current locations



- Even if Verizon Airfone were the sole ATG system, they would have to upgrade their system to use sectorized BTS and directional aero antennas to achieve sufficient capacity in the ATG.
- Coincidently, Verizon Airfone is already testing both directional aircraft antennas and 6-segment base station antennas using an 24 FCC experimental license.

Operation Below 10,000'

- Boeing has assumed that continuous coverage below 10,000' AGL is not a requirement for ATG systems
- We performed a technical analysis of commercial transport flights that shows 90% of flights spend less than 7 minutes below 10,000' at takeoff and less than 17 minutes on landing
- During the short time below 10,000', FAA regulations require passengers to shut-off and stow electronic devices.
- The proposed rules do not provide continuous coverage below 10,000'.
 - Technical & business solutions are possible.
 - Solutions can be worked out in cooperation with FCC and other service providers.

Summary & Conclusions

- There are 2 approaches that allow multiple service providers to share the ATG band using 3G (CDMA) technology:
 - Shared & highly coordinated base stations
 - Dispersed and uncoordinated base stations
- Both approaches achieve the following goals:
 - Capacity to serve entire market
 - Simple and affordable technology
- Boeing favors the latter approach to avoid the drawbacks of current ATG rules.
- Boeing has proposed new rules for the latter approach that require BTS to be separated.
- Boeing has found through simulation that the latter approach supports up to 4 systems using "plain-old" base station technology if the BTS are located on a regular grid.
 - In practice, the margin provided by backing off to 3 systems accommodates some grid irregularity for real-world BTS siting requirements.

DOCKET NO. 03-103

DOCUMENT OFF-LINE

This page has been substituted for one of the following:
o This document is confidential (NOT FOR PUBLIC INSPECTION)

- o An oversize page or document (such as a map) which was too large to be scanned into the ECFS system.
 - o Microfilm, microform, certain photographs or videotape.
- Other materials which, for one reason or another, could not be scanned into the ECFS system.

The actual document, page(s) or materials may be reviewed (EXCLUDING CONFIDENTIAL DOCUMENTS) by contacting an Information Technician at the FCC Reference Information Centers) at 445 12th Street, SW, Washington, DC, Room CY-A257. Please note the applicable docket or rulemaking number, document type and any other relevant information about the document in order to ensure speedy retrieval by the Information Technician

One CD